

Summary of Cost

Name of the Project:- Renovation at NRNA Building

Location :-Baluwatar, Kathmandu

Date: January 22, 2023

1. Quotation Details

| SN | Description | Amount (NRS) |
|----|-----------------------------------------------------|--------------|
| 1 | Total Cost for Boundary Wall | |
| 2 | Total Cost for Ramp Uplift for wheelchair (Lumpsum) | |
| | Grand Total: | - |

(Note: Amount sahl be inclusive of VAT)

Submitted By:

Company Name:

Address:

Contact Number:

Email address:

Submission Date:

Signature:

Company Seal:

BOQ

Project: Renovation at NRNA
Client: NRNA
Location: Baluwatar, Kathmandu
Date: January 22, 2023

(Note: All rates shall be inclusive of VAT)

| SN | Description of Work | Unit | Quantity | Rate | Amount | Remarks |
|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|------|--------|---------|
| 1 | Brick Soling | | | | | |
| 1.1 | Flat Brick Soling | | | | | |
| | Providing and laying one layer dry brick on flat soling in foundation and floor with approved chimney made first class brick in required line and level including filling joints with sand all complete as per drawings, specifications and instructions of the Engineer all complete. | Sqft | 112.82 | | | |
| 2 | Concreting Works | | | | | |
| 2.1 | Plain Cement Concrete (PCC): M10 (1:3:6) | | | | | |
| | Plain Cement concrete (PCC) in 1:3:6 ratio of Cement:sand:Aggregates, on floor with approved quality of cement and sand and crushed stone aggregate including mixing,laying,curing etc in line and level. | Sqft | 112.82 | | | |
| 2.2 | PCC for RCC: M20 (1:1.5:3) | | | | | |
| | Providing and laying of controlled reinforced cement concrete conforming to Grade M20 (1:1.5:3 ratio of Cement: Sand: Aggregates), with proper machine or hand mixed (as per requirement) with vibrating with vibrator as per necessity all complete. The cost shall include the cost for Machine mixing, Lifting, Placing, Machine vibrating, Curing etc. all complete in line and level as per drawings or specification all complete. | Cuft | 75.38 | | | |
| 3 | Formwork | | | | | |
| | Supply and Installation of formwork (commercial shuttering plyboards) with necessary stagings with proper props in line and level as per drawings and specification all complete. | Sqft | 150.75 | | | |
| 4 | Reinforcement | | | | | |
| | Supplying, straightening, cutting, bending, placing in position High yield strength (TMT bars) of all diameters to RCC work and binding with binding wire , all complete as per drawings and specifications. | Kg | 72.36 | | | |

| SN | Description of Work | Unit | Quantity | Rate | Amount | Remarks |
|--------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|------|--------|---------|
| 5 | Brickwork | | | | | |
| 5.1 | 9" Brickwork | | | | | |
| | Providing and laying Brick work in 1:6 (Cement: Sand) cement mortar including the cost of scaffolding, curing, raking, joint of one face and filing joint of another face. | Cuft | 250.28 | | | |
| 6 | Plaster Work | | | | | |
| 6.1 | External Plaster | | | | | |
| | Wall plaster in 18mm thk.cement sand (1:4) with uniform even, smooth finish, completely free from detect or trowel marks, vertical plumb face, straight and true to the line, with curing all in line and level including the necessary scaffolding. | Sqft | 536.00 | | | |
| 7 | Paint Work | | | | | |
| 7.1 | External Paint (Weathercoat Paint) | | | | | |
| | Supplying and applying two coat of weather coat emulsion paint, over required coat of primer, finished including surface preparation with smooth finishing including supply of materials, labour & Scaffolding all complete as per drawing, specification and instruction. | Sqft | 536.00 | | | |
| 8 | Metal Works | | | | | |
| 8.1 | Metal Fencing | | | | | |
| | Supply and installation of Metal fence on the boundary wall as per design or instruction of consultant inclusive of metal primer and enamel paint. | Sqft | 536.00 | | | |
| Grand Total for Bounday Wall: | | | | | - | |

Notes:

- 1 Please specify the brands of materials (cement, rebar, paint etc) wherever applicable in remarks column.